

**PURCHASE ORDER**

PHILIPPINE COUNCIL FOR AGRICULTURE AND FISHERIES

Telefax No. 927-8651

Supplier: <b>MARELCO TRADING CORP.</b>		P.O. No.: <b>04-033-23</b>			
Address: <b>Tagpuan sa Villa Escudero, Lalig, Tiaong, Quezon</b>		Date: <b>April 27, 2023</b>			
		Mode of Procurement: <b>Negotiated-Small Value Procurement</b>			
Gentlemen:					
Place of Delivery: <b>GSS, PCAF, DA Compound, Elliptical Rd., Diliman, Q.C.</b>		Delivery Term: <b>15 calendar days</b>			
Date of Delivery:		Payment Term: <b>One time payment</b>			
Stock/ Property No.	Unit	Description	Quantity	Unit Cost	Amount
	lot	KOLIN KLG5F405G1M - One (1) Unit 3-Tonner Floor Mounted Type Air Conditioning Unit (Conventional Type) inclusive of Supplies and Installation Fees	1	120,000.00	120,000.00
		3TR-Floor Mounted Type Air Conditioning Unit (Conventional Type)			
		Power Supply: 1-PH/230V/60HZ			
		Normal Capacity: 4.0HP/3 TR			
		Cooling Capacity: 37,980 kJ/h			
		Rated Current: 17.0A			
		Rated Power: 3,550 W			
		EER: 10.7KJ/hr-W			
		Refrigerant (type/charge): R-410A/2,450 g			
		Indoor Unit			
		Airflow (SH/Hj/Mi/Lo): 1,850/1,630/1,420/1,250 m <sup>3</sup> /hr			
		Sound Level (SH/Hj/Mi/Lo): 52/50/48/45db(A)			
		Unit Dimension (WxDxH): 589x408x1081 mm			
		Packaging Dimension (WxDxH): 735/2150/530mm			
		Unit Weight (Net/Gross):56/78.5kg			
		Outdoor Unit			
		Unit Dimension (WxDxH):980x427x790 mm			
		Packaging Dimension (WxDxH):1080x485x840 mm			
		Unit Weight (Net/Gross):70/75kg			
		Copper Tube Size			
		Low Side: $\varnothing$ 5/8"			
		High Side: $\varnothing$ 3/8"			
		Maximum Pipe Distance Between Indoor and Outdoor			
		Height: 10 m			
		Length: 30 m			



Stock/ Property No.	Unit	Description	Quantity	Unit Cost	Amount
		Supply and Installation Fees			
		1st 10 ft. installation charge			
		- Supply and installation of refrigerant pipe with rubber insulations			
		- Supply and installation of control wirings			
		- Supply and installation of PVC drain line			
		- Supply and installation of adequate clamp and hanger			
		- Supply and installation of ACCU bracket			
		- Test and observation			
		Additional charges			
		- Supply and installation of refrigerant pipe with rubber insulations			
		- Supply and installation of control wirings			
		- Supply and installation of weather proof circuit breaker 40 amps			
		x-x-x-x-nothing follows x-x-x-x-x			
		Purpose: For PDCD use.			
(Total Amount in Words)		One Hundred Twenty Thousand Pesos			120,000.00

In case of failure to make the full delivery within the time specified above, a penalty of one-tenth (1/10) of one percent for every day of delay shall be imposed on the undelivered item/s.

Conforme:

Very truly yours,

*Audelo R. Trivangco*  
 Signature over Printed Name of Supplier  
 5/10/23  
 Date

**NESTOR D. DOMENDEN**  
 Executive Director  
 4/4/23

Fund Cluster: 101  
 Funds Available: 120,000  
*Maria Divina P. Gonzales*  
**MARIA DIVINA P. GONZALES**  
 Chief Accountant

ORS/BURS No.: 06-107101-2023-05-047  
 Date of the ORS/BURS: 5/2  
 Amount: 120,000